

Premier Wall Systems

Drywall · Riverside Commercial Build-Out

CSI	Description	Qty	Unit	Unit\$	Amount
09 22 16	3-5/8in metal studs 25ga	12,400	SF	3.05	37,820.00
09 29 00	Gypsum board 5/8 Type X 2 sides	24,800	SF	1.72	42,656.00
09 29 00	Level 4 finish	24,800	SF	1.05	26,040.00
09 81 00	R-13 batt insulation	12,400	SF	0.78	9,672.00
07 84 00	Fire-stopping at rated walls	1	LS	7,800.00	7,800.00
			BID TOTAL: \$123,988.00		

Clarifications & Exclusions:

- 1. Excludes scaffolding/lifts.
- 2. Final cleaning by others.