

ACME DRYWALL & METAL FRAMING, LLC

1420 Industrial Pkwy, Columbus OH | bids@acmedrywall.com

SUBCONTRACTOR QUOTE · Quote #DW-2026-0417

Project: Maple Street Medical Office Building (3 storey)

To: Buckeye General Contractors Date: June 12, 2026

SCOPE OF WORK · Light gauge framing, gypsum board, taping & finishing

CSI	Description	Qty	Unit	Unit\$	Amount
09 22 16	Metal stud framing, 3-5/8" 25ga walls	12,400	SF	2.85	35,340.00
09 29 00	5/8" Type X gypsum board, both faces	24,800	SF	1.65	40,920.00
09 29 00	Tape & finish, Level 4	24,800	SF	0.95	23,560.00
09 81 00	Acoustic insulation, R-13 batts	12,400	SF	0.72	8,928.00
09 22 16	Ceiling suspension grid framing	9,200	SF	1.40	12,880.00

BASE BID TOTAL: \$121,628.00

CLARIFICATIONS & ASSUMPTIONS

1. Pricing assumes building dried-in and conditioned prior to board installation.
2. One mobilization included; additional mobilizations billed at \$850 each.
3. Pricing valid for 30 days from date above. Material escalation may apply thereafter.
4. Work is based on Architectural drawings dated 05/2026. Quantities by others; this proposal EXCLUDES fire-stopping/firecaulking at rated assemblies, scaffolding over 10', final cleaning, and removal/haul-off of construction debris (by others).
5. Add alternate ADD-1: Level 5 finish at lobby walls ADD \$6,200.00

Submitted by: J. Alvarez, Estimator