

Acme Drywall & Framing LLC

SUB-QUOTE · Trade: Drywall

Project: Riverside Commercial Build-Out

CSI	Description	Qty	Unit	Unit\$	Amount
09 22 16	Metal stud framing 3-5/8in 25ga	12,400	SF	2.85	35,340.00
09 29 00	5/8in Type X gypsum board both faces	24,800	SF	1.65	40,920.00
09 29 00	Tape and finish Level 4	24,800	SF	0.95	23,560.00
09 81 00	Acoustic insulation R-13 batts	12,400	SF	0.72	8,928.00
09 22 16	Ceiling suspension grid framing	9,200	SF	1.40	12,880.00

BID TOTAL: \$121,628.00

Clarifications & Exclusions:

- 1. Pricing assumes building dried-in prior to board installation.
- 2. This proposal EXCLUDES fire-stopping at rated assemblies, scaffolding over 10', and removal/haul-off of construction debris (by others).