

Apex Roofing Co

SPEC SECTION · Trade: Roofing

Project: Riverside Commercial Build-Out

CSI	Description	Qty	Unit	Unit\$	Amount
07 54 23	TPO membrane fully adhered 60 mil	22,000	SF	6.10	134,200.00
07 22 00	Polyiso roof insulation R-30	22,000	SF	2.30	50,600.00
07 62 00	Sheet metal flashing and trim	1,450	LF	14.00	20,300.00
BID TOTAL: \$205,100.00					

General: The roofing subcontractor shall furnish and install the membrane assembly described above. Wood blocking and nailers at perimeters are to be provided by others under the carpentry scope. Any structural deck repair discovered during tear-off is excluded and will be handled by change order. Interior finishes affected by leaks are not part of this scope.